

**RIDGE ROAD EXTENSION  
SUMMARY OF PAY ITEMS - PHASE I  
COUNTY PROJECT NO. C 6686.20**

| BRIDGE PAY ITEMS |   | UNIT | BRIDGE #1<br>NO. 144052 | BRIDGE #2<br>NO. 144053 | BRIDGE #3<br>NO. 144067 | BRIDGE #4<br>NO. 144068 | BRIDGE #5<br>NO. 144069 | BRIDGE #6<br>NO. 144070 | BRIDGE #7<br>NO. 144071 | BRIDGE #8<br>NO. 144072 | BRIDGE #9<br>NO. 144073 | BRIDGE #10<br>NO. 144074 | BRIDGE #11<br>NO. 144075 | BRIDGE #12<br>NO. 144076 | BRIDGE #13<br>NO. 144077 | BRIDGE #14<br>NO. 144078 | BRIDGE #15<br>NO. 144079 |
|------------------|---|------|-------------------------|-------------------------|-------------------------|-------------------------|-------------------------|-------------------------|-------------------------|-------------------------|-------------------------|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|--------------------------|
| 400-2-5          | Class II Concrete (Substructure)  | CY   | 994                     | 716                     | 296                     | 124                     | 409                     | 738                     | 260                     | 327                     | 510                     | 426                      | 324                      | 101                      | 145                      | 160                      | 230                      |
| 400-4-4          | Class IV concrete (Superstructure)  | CY   | 1487                    | 1018                    | 683                     | 211                     | 1040                    | 802                     | 236                     | 211                     | 532                     | 621                      | 729                      | 153                      | 269                      | 319                      | 568                      |
| 400-2-10         | Class II concrete (Approach Slab)   | CY   | 153                     | 117                     | 125                     | 96                      | 125                     | 96                      | 125                     | 96                      | 125                     | 96                       | 125                      | 96                       | 96                       | 125                      | 96                       |
| 400-9            | Bridge Deck Grooving & Planing, Deck 8.5" and Greater                           | SY   | 6558                    | 4515                    | 3176                    | 1149                    | 4639                    | 3566                    | 1339                    | 1149                    | 2553                    | 2824                     | 3363                     | 910                      | 1388                     | 1681                     | 2609                     |
| 400-147          | Composite Neoprene Pads   | CF   | 53                      | 39                      | 26                      | 10                      | 38                      | 32                      | 9                       | 10                      | 20                      | 27                       | 29                       | 7                        | 12                       | 12                       | 22                       |
| 415-1-4          | Reinforcing Steel (Superstructure)  | LBS  | 452074                  | 308304                  | 206727                  | 63764                   | 324235                  | 239009                  | 71025                   | 65870                   | 160287                  | 178863                   | 220900                   | 46451                    | 81580                    | 95610                    | 169815                   |
| 415-1-5          | Reinforcing Steel (Substructure)  | LBS  | 110421                  | 71160                   | 32333                   | 13232                   | 43014                   | 83389                   | 26240                   | 34116                   | 49794                   | 44688                    | 35553                    | 10893                    | 15568                    | 16991                    | 25220                    |
| 415-1-9          | Reinforcing Steel (Approach Slabs)  | LBS  | 29400                   | 25670                   | 24088                   | 18646                   | 24088                   | 18646                   | 24088                   | 18646                   | 24088                   | 18646                    | 24088                    | 18646                    | 18646                    | 24088                    | 18646                    |
| 450-1-1          | Prestressed Beams (AASHTO Type II)  | LF   | 5880                    | 4350                    | 2700                    | 900                     | 4110                    | 3425                    | 930                     | 900                     | 2100                    | 2650                     | 2880                     | 650                      | 1150                     | 1260                     | 2425                     |
| 455-34-3         | Prestressed Concrete Piling 18" SQ  | LF   | 690                     | 468                     | 0                       | 0                       | 0                       | 0                       | 0                       | 0                       | 0                       | 0                        | 0                        | 0                        | 0                        | 0                        | 0                        |
| 455-34-5         | Prestressed Concrete Piling 24" SQ  | LF   | 5828                    | 4300                    | 2721                    | 1054                    | 5518                    | 9465                    | 2106                    | 3845                    | 5949                    | 5186                     | 4606                     | 1172                     | 1787                     | 1886                     | 2255                     |
| 455-143-3        | Test Piles-Prestressed Concrete 18" SQ  | LF   | 130                     | 122                     | 0                       | 0                       | 0                       | 0                       | 0                       | 0                       | 0                       | 0                        | 0                        | 0                        | 0                        | 0                        | 0                        |
| 455-143-5        | Test Piles-Prestressed Concrete 24" SQ  | LF   | 453                     | 441                     | 242                     | 178                     | 478                     | 560                     | 149                     | 166                     | 250                     | 414                      | 402                      | 140                      | 231                      | 230                      | 238                      |
| 458-1-11         | Bridge Deck Expansion Joint, New Construction, F&I Poured Joint With Backer Rod | LF   | 479                     | 368                     | 224                     | 129                     | 336                     | 258                     | 168                     | 129                     | 224                     | 172                      | 280                      | 86                       | 129                      | 168                      | 172                      |
| 506-2            | Bridge Drain Pipe   | LF   | 0                       | 192                     | 357                     | 0                       | 552                     | 0                       | 178                     | 155                     | 139                     | 354                      | 0                        | 0                        | 0                        | 0                        | 249                      |
| 506-3            | Bridge Drains   | EA   | 0                       | 2                       | 2                       | 0                       | 3                       | 0                       | 0                       | 0                       | 1                       | 2                        | 0                        | 0                        | 0                        | 0                        | 2                        |
| 515-4-2          | Bullet Rail, Double Rail  | LF   | 1053                    | 0                       | 510                     | 0                       | 745                     | 0                       | 215                     | 0                       | 410                     | 0                        | 540                      | 0                        | 0                        | 270                      | 0                        |
| 521-5-1          | Concrete Traffic Railing- Bridge (32" F-Shape) Index 420                        | LF   | 2106                    | 1886                    | 1020                    | 480                     | 1490                    | 1490                    | 430                     | 480                     | 820                     | 1180                     | 1080                     | 380                      | 580                      | 540                      | 1090                     |
| 521-6-11         | Concrete Parapet, Pedestrian/Bicycle, 27" Height                                | LF   | 1053                    | 0                       | 510                     | 0                       | 745                     | 0                       | 215                     | 0                       | 410                     | 0                        | 540                      | 0                        | 0                        | 270                      | 0                        |
| 530-1            | RipRap, Sand Cement   | CY   | 75                      | 67                      | 0                       | 0                       | 0                       | 0                       | 0                       | 0                       | 0                       | 0                        | 31                       | 55                       | 0                        | 0                        | 0                        |
| 530-3-3          | RipRap- Rubble, Bank and Shore  | TN   | 910                     | 808                     | 0                       | 0                       | 0                       | 0                       | 0                       | 0                       | 0                       | 0                        | 439                      | 780                      | 0                        | 0                        | 0                        |
| 530-74           | Bedding Stone   | TN   | 419                     | 372                     | 0                       | 0                       | 0                       | 0                       | 0                       | 0                       | 0                       | 0                        | 202                      | 359                      | 0                        | 0                        | 0                        |
| 548-12           | Retaining Walls (MSE)   | SF   | 0                       | 0                       | 1624                    | 1442                    | 1624                    | 1442                    | 1276                    | 1133                    | 1276                    | 1133                     | 5456                     | 4488                     | 4488                     | 3480                     | 2060                     |
| 550-10-344       | Fencing, Type R, 7.1-8.0, w/Partial Enclosure                                   | LF   | 1053                    | 0                       | 510                     | 0                       | 745                     | 0                       | 215                     | 0                       | 410                     | 0                        | 540                      | 0                        | 0                        | 270                      | 0                        |
|                  |   |      |                         |                         |                         |                         |                         |                         |                         |                         |                         |                          |                          |                          |                          |                          |                          |
|                  |   |      |                         |                         |                         |                         |                         |                         |                         |                         |                         |                          |                          |                          |                          |                          |                          |
|                  |   |      |                         |                         |                         |                         |                         |                         |                         |                         |                         |                          |                          |                          |                          |                          |                          |
|                  |   |      |                         |                         |                         |                         |                         |                         |                         |                         |                         |                          |                          |                          |                          |                          |                          |

PAYMENTS FOR INCIDENTAL ITEMS NOT SPECIFICALLY COVERED IN THE INDIVIDUAL BID ITEMS SHALL BE INCLUDED IN THE CONTRACT PRICES FOR BID ITEMS.

**REVISIONS**

| DATE | BY | DESCRIPTION | DATE | BY | DESCRIPTION |
|------|----|-------------|------|----|-------------|
|      |    |             |      |    |             |

Wendy G. Snow P.E. No. 81114  
NV5 Inc.  
1713 S. Kings Ave, Brandon, FL 33511  
Certificate of Authorization No. 29065

PASCO COUNTY, FLORIDA

ROAD NO. COUNTY PROJECT NUMBER  
CR-524 C 6686.06

**SUMMARY OF PAY ITEMS**

SHEET NO. A-5